



Stantec Consulting Services Inc.
3 Columbia Circle, Suite 6
Albany NY 12203-5158

Addendum

Project/File: TONS Generators
Addendum No.: Addendum No. 1
Date: July 16, 2025
To: Bidders
Contract No.: Town of New Scotland Generator Supply

This addendum is to be read with and constitutes part of the tender document.

Instructions:

1. Amend your copy of the tender/quotation/proposal in accordance with the detail below.
2. Retain one copy for your file; sign and return a second copy and attach to your submission as confirmation that the Addendum was taken into account in your bid submission.
3. Failure to sign and return this form may result in a non-compliant bid.

Details of the Addendum:

1. In the Request for Bid document it said: Plans and Specifications will be made available to prospective bidders electronically on July 8, 2025. Just wanted to check about the plans.
Response: No plans are available for this RFP.
2. Are all of the generators going to be installed outside on a concrete slab?
Response: All generators will be installed outside on a concrete pad. However, this RFP is for the supply and delivery only of the generators to each site location. Installation and rigging the generators will be under a separate RFP.
3. In the specs it mentions the sound level be below 78dBA at 23 feet and then later says below 70dBA for 60kW and below and 76dBA for 100kW.
Response: The sound level should be below 70dBA for the 40, 50, and 60kW generators, for the 100kW generator it should be 76dBA or less – all at a distance of 23 feet. Disregard the 78dBA level listed within Section 2.4.G.2 of the specifications.
4. Section 1.1.A.6 references loadbanks. There are no other mentions of loadbanks on the rest of the specs. Please confirm if loadbanks are required.
Response: Load banks are not required and not included within the spec, please disregard it in the summary section.
5. For typical pump stations that are remotely operated, we have not seen genset nor ats annunciators installed. Please advise if this is a requirement. Our genset & ATS have form c contacts which can be tied into the local facility BMS for telemetry/monitoring.

Response: Yes, remote monitoring should be provided for operation and notification of the system.

6. Please confirm this bid is to only furnish and deliver to jobsites. Installation & rigging is provided by the Town's electrical Contractor.

Response: Yes, that is correct. The installation and rigging of the generator will be under a separate contract. The vendor/manufacturer shall be present for required commissioning and testing and that service should be included within the bid.

Sincerely,

Stantec Consulting Services Inc.



Troy Wojciekofsky, PE

Senior Project Manager
Phone: (518) 452-4358
troy.wojciekofsky@stantec.com

stantec.com

c.

Firm Name:

Authorized Signature:

Printed Name:

Date:

July 16, 2025
